

1 070804

4-30

API NUMBER 15-145-20,970.0000

NE NW NE, SEC. 4, T 20 S, R 16 W/E

4950 feet from S section line

1650 feet from E section line

Lease Name Hagerman Well # 2

County Pawnee 121.71

Well Total Depth 3745 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1053 w/450 sx circulated

TECHNICIAN'S PLUGGING REPORT

Operator License # 6563

Operator: Double "B" Oil, Inc.

Name & Address 200 West Douglas, Suite 240

Wichita, KS 67202

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Double "B" Oil, Inc. License Number 6563

Address 200 West Douglas, Suite 240, Wichita, KS 67202

Company to plug at: Hour: 9:45 a.m. Day: 30 Month: 4 Year: 19 90

Plugging proposal received from Jim Line

(company name) Double "B" Oil, Inc. (phone) 316-264-2891

were: 5 1/2" at 3741' PBD 3738' Perfs at 3719-22, 3731-35'

1st plug pump 400 lbs. hulls and 300 sx cement down 5 1/2".

2nd plug pump 100 sx cement down 5 1/2" X 8 5/8" annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:50 a.m. Day: 30 Month: 4 Year: 1990

ACTUAL PLUGGING REPORT 1st plug pumped 350 lbs. hulls and 300 sx cement down 5 1/2".

Maximum pressure 1000 psi and shut in 500 psi.

2nd plug pumped 150 lbs. hulls and 100 sx cement down backside. Maximum pressure

750 psi and shut in 400 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-16-90

INV. NO. 28152

observe this plugging.

MAY 09 1990

5-9-90

Signed Dan Godrow (TECHNICIAN)

STATE CORPORATION COMMISSION CONSERVATION DIVISION Wichita, Kansas