

To: 1 071056 4-23  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-145-20,902.0000  
NE NW SW, SEC. 4, T. 20 S, R. 16 W/E  
2310 feet from S section line  
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 6563  
Operator: Double "B" Oil Inc.  
Name & Address: 155 N. Market, Suite 710  
Wichita, KS 67202

Lease Name Bowman Well # 1  
County Pawnee  
Well Total Depth 3801 123.53 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 846

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:50 a.m. Day: 23 Month: 4 Year: 1992

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 3799' w/100 sx cement, Open hole 3799-3801'

1st plug sand back to 3740' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:30 a.m. Day: 23 Month: 4 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 3740' and dumped 4 sx cement on top  
of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,  
100 lbs. hulls and 150 sx cement.

Maximum pressure 1000 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1600' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE 5-12-92

INV. NO. 35208

Signed Dan Jordan  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
RECEIVED  
APR 28 1992  
CONSERVATION DIVISION  
Wichita, Kansas