

No: 1 120361
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-10
API NUMBER 15- 145-20,440.0000
SW NW NE, SEC. 4, T 20 S, R 16 (W) X
4290 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6563
Operator: Double B Oil, Inc.
Name & Address: 300 West Douglas, Suite 320
Wichita, KS 67202

Lease Name Haggerman Well # 1
County Pawnee 123.40
Well Total Depth 3797 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1075

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers, Inc. License Number 4635
Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 11:30 a.m. Day: 10 Month: 1 Year: 19 90

Plugging proposal received from Gary Burke
(company name) Great Bend Casing Pullers, Inc. (phone) 316-793-9711

were: 4 1/2" at 3793' Perfs at 3787-89'
1st plug sand back to 3730' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 9 sx gel, 75 sx cement, 11 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:30 p.m. Day: 10 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3730' and dumped 4 sx cement
on top of sand through bailer,
2nd plug pumped into 8 5/8" surface casing with 400 lbs. hulls, 9 sx gel, 75 sx cement,
11 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Pumping pressure 0-1000 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1640' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
JAN 24 1990
observe this plugging.

Signed Duane Rankin (TECHNICIAN)

DATE

INV. NO. 27115