

To: 1 080094. 15.135.00148.0000 API NUMBER 15- Drilled 12/20/57

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

NW NW SE, SEC. 14, T 20 S, R 24 W X  
2310 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License / 9615

Lease Name Petersilie A Well # 1

Operator: Joe Gerstner Oil  
Name & Address RR 1, Box 115A  
Ness City, KS 67560

County Ness  
Well Total Depth 4405 143.16 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 361

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A

Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901

Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 2:30 p.m. Day: 18 Month: 12 Year: 19 96

Plugging proposal received from Kent Strube

(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

logs: 5 1/2" at 4391', PBTB 4395', Open hole 4391-4405'

1st plug had casing leak-tag and pump 5 sx cement,

2nd plug run 2 3/8" tubing to 796', perforate at 800', pump 20 sx gel, 250 lbs. hulls, 150 lbs.

hulls mixed in cement, circulate to surface.

Plugging Proposal Received by Kevin Strube  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3:45 p.m. Day: 18 Month: 12 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug (had casing leak) tagged up at 3000' and pumped 5 sx cement,

Casing parted at 400'; 2nd plug ran 2 3/8" tubing to 796'. Log Tech perforated at 800' and

ran shot down tubing. Pumped 20 sx gel with 250 lbs. hulls mixed in. Started cement.

Mixed in 150 lbs. hulls with first of 310 sx cement. Circulated to surface.

12-23-96

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

(Do not ~~check~~ observe this plugging.)

Signed Kevin D Strube  
(TECHNICIAN)

INVOICED  
DATE JAN 02 1997  
INV. NO. 47214