

To: 1 080093
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 135-21,834-0000
W/2 SE, SEC. 14, T 20 S, R 24 W/E
1320 feet from S section line
1980 feet from E section line

12-19
TECHNICIAN'S PLUGGING REPORT
Operator License # 9615
Operator: Joe Gerstner Oil Company
Name & Address: RR 1, Box 115A
Ness City, KS 67560

Lease Name Petersilie A Well # 8
County Ness
Well Total Depth 4390 142.6' feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 567

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 3:45 p.m. Day: 19 Month: 12 Year: 19 96

Plugging proposal received from Pat Gerstner
(company name) Joe Gerstner Oil Company (phone) 913-798-2893

Work: 4 1/2" at 4387' w/225 sx cement, Open hole 4387-4390', Squeezed at 840' w/200 sx cement
1st plug pump 25 sx cement with 300 lbs. hulls to 1600', cement to surface,
2nd plug pump 50 sx cement down backside.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:45 p.m. Day: 19 Month: 12 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped 200 lbs. hulls and 25 sx cement, 14 sx gel,
and 160 sx cement. Maximum pressure 600 psi and shut in 100 psi.

2nd plug went down 8.5/8" X 4 1/2" with 5 sx cement. Shut in pressure 500 psi.

12-23-96
Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

1 (if not observed) observe this plugging.

Signed Kevin D. Strube (TECHNICIAN)

INVOICED
DATE JAN 02 1997
INV. NO. 47213