

To: 1071025
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 15.135.30182.0000 21
Drilled 2/17/66

TECHNICIAN'S PLUGGING REPORT

Operator License # 9615
Operator: Joe Gerstner Oil
Name & Address RR 1 Box 115 A
Ness City, KS 67560

SW SE SE, SEC. 14, T. 20 S, R. 24 W/E
330 feet from S section line
990 feet from E section line
Lease Name Petersilie Well # 5
County Ness
Well Total Depth 4382 142.41 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 279

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Joe Gerstner Oil License Number 9615
Address RR 1, Box 115 A, Ness City, KS 67560

Company to plug at: Hour: 2 p.m. Day: 6 Month: 2 Year: 19 92

Plugging proposal received from Pat Gerstner
(company name) Joe Gerstner Oil (phone) 913-798-2893

were: 4 1/2" at 4374' w/125 sx cement. PBSD 4300'. Perfs at 4259-77'
1st plug push plug to tag point, dump 15 gal. of sand, bail in 10 sx cement,
2nd plug run tubing to 800' and circulate 50 sx cement,
3rd plug pull tubing, pump 100 sx cement down 4 1/2",
4th plug pump 100 sx cement down backside.

RECEIVED
STATE CORPORATION COMMISSION

FEB 13 1992

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 6:15 p.m. Day: 6 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pushed plug to tag point at 2200', dumped 15 gallons of sand, bailed in 10 sx cement,

Junk in hole, casing eaten up and full of holes
2nd plug ran tubing to 800' and circulated 50 sx cement,
3rd plug pulled tubing, pumped 100 sx cement down 4 1/2". Maximum pressure 100 psi and shut in on vacuum. 4th plug pumped 100 sx cement down backside. Maximum pressure 500 psi and shut in 0 ps:

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery. Several squeeze jobs were done
(if additional description is necessary, use BACK of this form.) in past.

INVOICED

DATE MAR 10 1992
INV. NO. 34711
2-6

Signed Dan Johnson (TECHNICIAN)