

To: 1080015
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-6/27/58 15.135.00669.0000
SE SE NW, SEC. 14, T 20 S, R 24 ~~W~~

2-12

2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9615
Operator: Joe Gerstner Oil
Name: _____
Address RR 1, Box 115A
Ness City, KS 67560

Lease Name Petersilie B Well # I
County Ness
Well Total Depth 4457 144.85 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 356

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well at hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____

Address Ness City

Company Joe Gerstner Oil Plug at: Hour: 10:15 a.m. Day: 12 Month: 2 Year: 1996

Plugging proposal received from Joe Gerstner
(company name) Joe Gerstner Oil (phone) 913-798-2893

Work: 5 1/2" at 4457', PBTD 4435', Perfs at 4410-20'; Well squeezed at 1100' w/150 sx & 2400' w/150 sx cm

1st plug pump down 5 1/2" with 300 lbs. hulls, 25 sx cement, 25 sx gel, and 85 sx cement.

2nd plug pump 50 sx cement down backside.

Plugging Proposal Received by Kevin Strube
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 12 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" with 300 lbs. hulls, 25 sx cement, 25 sx gel, and 85 sx cement. Maximum pressure 800 psi and shut in 500 psi.

2nd plug pumped 50 sx cement down 8 5/8" X 5 1/2". Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

(Do not XXXXXXXX) observe this plugging.

DATE 2-27-96

INV. NO. 44892

2-12

Signed Kevin P. Strube
(TECHNICIAN)

RECEIVED
KANSAS CORP COMM
1996 FEB 20 A 11:28

2-20-96