

15.135.2218-0.0000

To: 1 060086

STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- Drill completion 8/29/58x

SE SW NE, SEC. 14, T 20 S, R 24 WXX

RECEIVED  
KANSAS CORP COMM

2970<sup>x</sup> feet from S section line

1650<sup>x</sup> feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 31627 1998 JAN 22 12:12 Lease Name Petersilie A Well # 1

Operator: Whitetail Crude, Inc. 1-22-98 County Ness 144.92

Name & Address P.O. Box 544 Well Total Depth 4459<sup>x</sup> feet

Ness City, KS 67560-0544 Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 508<sup>x</sup>

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ O&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Allied Cementing License Number \_\_\_\_\_

Address P.O. Box 420, Ness City, KS 67560

Company to plug at: Hour: 8:30 a.m. Day: 20 Month: 1 Year: 19 98

Plugging proposal received from Mike Fritzler

(company name) Whitetail Crude, Inc. (phone) 785-798-3641

Work: 5 1/2" at 4458', Perfs at 4386-92', Squeezed at 600-700' with 250 sx cement

1st plug pump 35 sx cement with 100 lbs. hulls,

2nd plug pull tubing to 1500', pump 165 sx cement,

Check backside.

Plugging Proposal Received by Mike Maier  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12:30 p.m. Day: 20 Month: 1 Year: 19 98

ACTUAL PLUGGING REPORT 1st plug pumped 35 sx cement with 100 lbs. hulls on bottom,

2nd plug pulled tubing up to 1500', pumped 165 sx cement, lost circulation. Pulled tubing.

3rd plug went down backside with 10 sx cement. Shut off with 500 psi.

4th plug pumped 80 sx cement with 200 lbs. hulls down casing and filled it up.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(old / ~~XXXXXX~~) observe this plugging.

DATE 1-23-98

INV. NO. 49984

1-20

Signed Michael Maier  
(TECHNICIAN)