



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. - 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 JAN 4 1972  
 CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Gibson of Leben Drlg. has this

date requested permission to plug the following described well:

Mr. Gibson guarantees payment of the plugging fee.

Operator's full Name: Aspen Drlg., Co.

Complete Address: Box 783 Great Bend, Ks.

Lease Name: Petersillie Well No. 1

Location: C NE NE Sec. 14 Twp. 20 Rge. (E)(W) 24

County: Ness Total Depth 4430' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Gibson was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing ~~XXXXXXX~~

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Manning  
 Conservation Division Agent