

State of Kansas



15-135-30233-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 21 1966
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Pfannenstiel of Leben Drilling Company has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Meltzer Oil Company

Complete Address: Drawer "B" Great Bend Kansas

Lease Name: Petersillie "A" Well No. 6

Location: SE SW SE Sec. 14 Twp. 20 Rge. 24 (E)(W) X

County Ness Total Depth 1342 Oil Well

Gas Well Input Well SWD Well D & A Lost Hole X

Mr. Pfannenstiel was instructed to plug the well as follows:

Surface pipe collapsed. Milled over and cut off at 30 Ft.

Wash down to top of fish with 12 1/2" rock bit run pipe to 280 Ft. and displace 20 sc cement thru pipe. Mud to 30 Ft. and fill to bottom of surface with 40 sc cement. If pipe will not go inside 8 5/8 csg.

cement thru 1 Jt. drill pipe from top of fish (30 Ft.) to base of celler with 60 sc cement with pump truck. Plug rat hole with 2 sc cement.

Very truly yours,

Leo Massey
Conservation Division Agent