

15.145.00993.0001

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 8 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kathol Petroleum, Inc.
Complete Address 900 Sutton Place Wichita, Kansas 67202
Lease Name Hagerman "A" Well No. 3 (SWD)
Location SW NE NW Sec. 4 Twp. 20 Rge. (E) (W) 16
County Pawnee Total Depth 3806
Abandoned Oil Well Gas Well Input Well SWD Well XXX D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools
Address License No.
Operation Completed: Hour 11.30 A Day 4 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3806' 8 5/8 csg set at 804' cwc 350 sk.
5 1/2 csg set at 3805' cw 100 sk cmt.
5 1/2 csg squeezed at 300' with 100 sk cmt.
4 1/2 liner set at 3321'. Perf. at 866' and squeezed.
No pipe recovered.
Pumped down 4 1/2 csg with 20 sk cmt, 25 sk gel W/2 sk hulls, plug and 45 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 9/8/70
INV. NO. 2498-W