

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Kathol Petroleum, Inc.

Complete Address: 900 Sutton Place Wichita, Kansas

Lease Name Hanken Well No. 1

Location NE NE SW Sec. 4 Twp. 20 Rge. 16 (E) (W) X

County Pawnee Total Depth 3719'

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Ralph Comstock Pipe Pulling

Address: Stafford, Kansas License No. 490

Operation Completed: Hour \_\_\_\_\_ Day \_\_\_\_\_ Month \_\_\_\_\_ Year \_\_\_\_\_

The Above well was plugged as follows:

Total Depth 3719' 8 5/8 csg set at 868' cwc

5 1/2 csg set at 3708' cw 100 sc cmt.

Filled 5 1/2 csg W/sand (3690-3719) Dumped 5 sc cmt W/dump bailer (3650-90)

Shotoff and recov. 2650' of 5 1/2 csg.

Pumped thru 8 5/8 plg container with 20 sc gel W/3 sc hulls, plug and 100 sc 50-50

poz cement W/6% total gel. Max. pres. 500 lbs. SI pres. 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 11/22/68

INV. NO. 8863-W