

15.145.00717-0000

Form CP-3
Rev. 6-26-62

KANSAS

JP

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Kathol Petroleum, Inc.

Complete Address: 900 Sutton Place Wichita, Kansas 67202

Lease Name Hagerman Well No. 2-A

Location NE NE NW Sec. 4 Twp. 20 Rge. (E) (W) 16

County Pawnee Total Depth 3760'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ralph Comstock Pipe Pulling

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 3:30P Day 7 Month 10 Year 1969

The Above well was plugged as follows:

Total Depth 3760' 8 5/8 csg set at 718' cwc

5 1/2 csg set at 3756' cw 150 sk cmt.

Filled 5 1/2 csg W/sd (3740-3760) Dumped 5 sk cmt W/dump bailer. (3700-3740)

Cutoff and recovered 2000' of 5 1/2 csg.

Pumped thru 8 5/8 plug container With 20 sk gel W/5 sk hulls, plug and 100 sk 50-50 poz

cmt W/6% total gel. Max. pres. 300 lbs. SI pres 150 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/9/69

INV. NO. 616-u

Signed: Red F. Massey
Well Plugging Supervisor