

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 25 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Kathol Petroleum, Inc.

Complete Address: 900 Sutton Place Wichita, Kansas 67202

Lease Name Hagerman Well No. A-1

Location NE SE NW Sec. 4 Twp. 20 Rge. 16 (E) (W) XX

County Pawnee Total Depth 3756

Abandoned Oil Well XX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Comstock Pipe Pulling

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 4P Day 23 Month 11 Year 1968

The Above well was plugged as follows:

Total Depth 3756' 8 5/8 csg set at 841' cwc 350 sc.

5 1/2 csg set at 3736' cw 150 sc.

5 1/2 csg filled with sand (3700-3756) Dumped 5 sc cmt W/dump bailer (3660-3700)

Dakato section squeezed. Recov. 160' of 5 1/2 csg.

Filled 8 5/8 csg with readymix cement (2 1/2 yds) from (0-160)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo R. Munn  
Well Plugging Supervisor

DATE 11/26/68  
INV. NO. 8873-4