

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE-NE-NE

SEC. 4 TWP. 20 RGE. 16-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Hagerman

Operator Berwick Spruill & Horus Address Great Bend - Kansas

Field _____ County Pawnee

Total Depth 3747 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/8 - 1078 ft. Circulated with Cement
5/8 casing set at 3734 ft. Plugged back lower bottom
to 3645 ft with sand & rock - 5 sacks of cement
Mudfill at 3645 ft inside the 5/8 casing - Shot off &
Pulled 200 ft of 5/8 casing - Filled with mud to 900 ft
Bridges & 28 sacks of cement. Mud to 200 ft. Bridges &
15 sacks of cement. Mud to 20 ft. Plug & 8 sacks Cement.*

J. Farves Pipe Pulling Contractor

C. D. Stough
District Conservation Agent

Date 6-13-48

PLUGGING
FILE SEC 4 T 20 R 16W
BOOK PAGE 34 LINE 41

6-5-48

1948

F