

KANSAS

Form CP-3

Rev. 6-4-68

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

JUN 28 1978

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 135 - 21,490.0000 (of this well)

Operator's Full Name Pendleton Land & Development, Inc.

Complete Address 1410 Security Life Bldg., Denver, Colorado

Lease Name Petersillie Well No. 1

Location SW NE NW Sec. 14 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4500'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Buffalo Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 3:30 P Day 26 Month 6 Year 1978

The above well was plugged as follows:

RTD 4500' 8 5/8 csg. set 414' cwc Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 600' thru drill pipe.

Heavy mud to 300' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6-28-78

Signed: Geo Messerly  
Well Plugging Supervisor

INV. NO. 7583-W