

KANSAS

R STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Aspen Drilling Company

Complete Address Box 783 Great Bend, Kansas 67530

Lease Name Petersilie Well No. 1

Location C NE NE Sec. 14 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4430'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Leben Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 12:45 P Day 2 Month 1 Year 1971

The above well was plugged as follows:

RTD 4430' 8 5/8 csg set at 292' cwc Cmt. Mat. 50-50 poz cmt W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4931-42