

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAY 04 1976

5-4-76

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - -

CONSERVATION DIVISION
Wichita, Kansas
(of this well)

Operator's Full Name Meltzer Oil Co.

Complete Address Drawer "B", Great Bend, Kansas 67530

Lease Name Petersilie "A" Well No. 6

Location SE SW SE Sec. 14 Twp. 20 Rge. (E) (W) 24

County Ness Total Depth 4384'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Great Bend, Kansas 67530 License No. 462

Operation Completed: Hour 10:15 A Day 3 Month 5 Year 1976

The above well was plugged as follows:

Total Depth 4384' 8 5/8 csg set 2861' cwccl 190 sk.

4 1/2 csg set 4381' cw 225 sk cem.

4 1/2 csg squeezed A/900' W/300 sk cem.

4 1/2 csg filled W/sd to 3000' -dumped 4 sk cem W/dump bailer. (3000-2960)

Shotoff & recovered 335' of 4 1/2 csg.

~~Advised~~
~~XXXXXX~~ Cementing Co. pumped down 8 5/8 csg with 10 sk gel & water W/300 lbs hulls-

released 8 5/8 plug & pumped 120 sk Comm Cem. 4% gel. PP 900 lbs. SIP 750 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo Wassuy
Well Plugging Supervisor

DATE 5-04-76

INV. NO. 3159-W