

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 11-33

LOCATION NE-NE-NW

SEC. 28 TWP. 16 RGE. 25W

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Mc Clean

Operator Rooney-Siegfried & Thomas Address Box 324 Great Bend Kans.

Field _____ County Ness

Total Depth 4547 Feet.

Plugging Contractor H. O. Casing Pulling Co.

Plugging Contractor's License No. 206

Address ? _____

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8" (4) 280' C.W.C. Oil String 5 1/2" O.D.
4540' w/150 sq Cem. P.B. to 4530' Top plug 4523'
Dump 10 sq Cem on plug at 4530. Shut off and
pulled 5 1/2" casing. Filled hole with mud to 275'
set 10' rock bridge and run 20 sq Cem with
dump barrels mud to 35' r. bridge and 10 sq
Cem to base of collar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 17 1954
2-19-54

Warren H. Horner
District Conservation Agent

Date Feb 17, 1954

PLUGGING
FILE SEC 28 T 16 R 25W
BOOK PAGE 11 LINE 83

CONSERVATION DIVISION
Wichita, Kansas