

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

200 Colorado Derby Bldg.
Wichita, KS 67202

API Number 15-135-21,962.00.00

Operator's Full Name KENNEDY - MITCHELL, INC.

Complete Address 7400 WEST JEFFERSON AVE. - DENVER, COLORADO.

Lease Name STEPHEN'S Well No. #38-619

Location SE-NE-SE Sec. 35 Twp. 16 Rge. 21 (East) (West)

County NESS Total Depth 4200 ^{FE}

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor DAMAC DRILLING, INC

Address BOX 1164 GREAT BEND, KS License No. _____

Operation Completed: Hour: 2:00 AM Day: 25th Month: MAY Year: 19 81

Plugging Operations attended by Agent? All Part None ORDERS, BY THOMAS.

The above well was plugged as follows:

- 8 5/8" 410 FE SP CUL
- ORDERED 150 ST 50/50 POZMIX - 2% GEL - 3% CA-CL. + 8 5/8" PLUG.
- SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
- 1ST PLUG. @ 1500 FE W/ 80 ST CNT.
- 2ND PLUG. @ 400 FE W/ 50 ST CNT.
- 3RD PLUG. - SOLID BRIDGE @ 40 FE W/ 0 W/ 10 ST CNT.
- 5ST IN RAT HOLE
- 5ST IN MOUSE HOLE.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6-25-81

INV. NO. 5732-W

Signed: [Signature]
Conservation Division Agent ORDERS BY THOMAS.

STATE CORPORATION COMMISSION
RECEIVED
MAY 28 1981
CONSERVATION DIVISION
Wichita, Kansas