

KANSAS

J.P.
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

JAN 5 1968

Operator's Full Name Chief Drilling Company

Complete Address Box 797 Great Bend, Kansas

Lease Name Starrett Well No. 2

Location C NE SW Sec. 34 Twp. 16 Rge. 21 (E) (W) X

County Ness Total Depth 4190

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Co. Tools

Address License No.

Operation Completed: Hour 7 P Day 3 Month 1 Year 1968

The above well was plugged as follows:

RTD 4190' 8 5/8 csg. set at 285' cwc 225 sc. Cem. Mat. 50-50 poz W6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem. thru drill pipe. Heavy mud to 280' set cementing plug and displaced 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. J. Messer
Well Plugging Supervisor

DATE 1/5/68
INV. NO. 7050-W