

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

*R*

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name ABERCROMBIE DRILLING INC

Complete Address 801 UNION CENTER - WICHITA, KANS. 67202

Lease Name LAMER Well No. #1

Location C-SE-NW-NW Sec. 26 Twp. 16 Rge. 21 (E) (W) W

County NESS Total Depth 4210 <sup>FE</sup>

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor KELSO CASING PULLERS INC

Address BOX 176 CHASE, KANS. 67524 License No. 176

Operation Completed: Hour 10:15 <sup>PM</sup> Day 24 <sup>th</sup> Month JAN. Year 1980

The above well was plugged as follows:

8 5/8" 475 FE CUC. - 5 1/2" SET AT 4209 FE - PERFS TO 4119 FE  
5 1/2" BRIDGED OFF AT 1821 FE PIPE PULLERS COULDN'T GET ANY DEEPER  
WITH BAILER - SET PLUG. AT 1821 FE WITH SAND AND 5<sup>th</sup> CMF.  
SHOT PIPE SEVERAL TIMES - RECOVERED 1644 FE.  
ORDERED 135<sup>th</sup> 5/8 Pozmix 6% GEL. -> 20<sup>th</sup> GEL. -> 4<sup>th</sup> HULLS -> 4 8 5/8 PLUG.  
PUMPED IN WITH PUMP TRUCK. -> PUT IN - 2<sup>th</sup> HULLS - 14<sup>th</sup> GEL - 70<sup>th</sup> CMF.  
6<sup>th</sup> GEL - 2<sup>th</sup> HULLS - RELEASED PLUG. AND 65<sup>th</sup> CMF.  
MAX. PRESSURE 700<sup>lbs</sup> SHUT IN 350<sup>lbs</sup> -> CEMENTED BY FLUID CEMENTING

I hereby certify that the above well was plugged as herein stated.

NOTICED

1-28-80

INV. NO. 1444-W

Signed: Marion Schmitt  
Well Plugging Supervisor

JAN 28 1980 1-28-80