

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1967

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bank Bldg. Wichita, Kansas

Lease Name Harms-Kendall "B" Well No. 1

Location C SW NE Sec. 10 Twp. 16 Rge. 21 (E) (W) X

County Ness Total Depth 4300

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No.

Operation Completed: Hour 3:30 P Day 20 Month 9 Year 1967

The Above well was plugged as follows:

RTD 4300' 8 5/8 csg set at 245' cwc 150 sc.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 100 sc cem.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/22/67

INV. NO. 6366-w

Signed: [Signature]
Well Plugging Supervisor