

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1968
CONSERVATION DIVISION
Wichita, Kansas

3600

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 4th Nat'l Bk. Bldg. Wichita, Kansas

Lease Name Harms - Kendall "E" Well No. 1

Location C W/2 NW SE Sec. 10 Twp. 16 Rge. 21 (E) (W) X

County Ness Total Depth 4266

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Russ Casing Pulling

Address: Box 1082 Great Bend, Kansas License No. 623

Operation Completed: Hour 3P Day 25 Month 10 Year 1968

The Above well was plugged as follows:

Total Depth 4266' 8 5/8 csg set at 244' cwc. 185 sc.

4 1/2 csg set at 4262' cw 100 sc cmt.

4 1/2 csg PBSD 4238' with top perf. 4207'

Filled 4 1/2 csg with sand (4190 - 4238) Dumped 4 sc cmt with dump bailer. (4070 - 4190)

Shotoff and recov. 3600' of 4 1/2 csg.

Pumped thru 8 5/8 plug container with 25 sc gel W/5 sc hulls, plug and 140 sc 50-50

poz cement with 6% total gel. Max pres. 600 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/28/68

INV. NO. 8916-10

Signed: Geo F. Massey
Well Plugging Supervisor