

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN - 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Champlin Petroleum Company

Complete Address P. O. Box 308 Ellinwood, Kansas

Lease Name Harms-Kendall "B" Well No. 1

Location C E/2 NE NW Sec. 10 Twp. 16 Rge. 21 (E) (W) X

County Ness Total Depth 4286'  
4190'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Garvey Drlg.

Address Wichita, Ks. License No.       

Operation Completed: Hour 2 A Day 6 Month 1 Year 1968

The above well was plugged as follows:

RTD 4190' 8 5/8 csg set at 250' cwc 165 sc. Cementing Material 50-50 POZ W/6% Gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sc cem.

thru drill pipe. Heavy mud to 280' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE 1/8/68  
INV. NO. 9065-U