

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 25 1972

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas

Lease Name Oetken Well No. 1

Location App. C SW SW SE Sec. 5 Twp. 20 Rge. (E) (W) 16

County Pawnee Total Depth 3865'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co., Inc.

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 11:30 A Day 22 Month 7 Year 1972

The above well was plugged as follows:

Total Depth 3865' 8 5/8 csg set at 1120' cwc 550 sk.

5 1/2 csg set at 3864' cw 125 sk cmt.

5 1/2 csg PBDT 3846' with top perf. (3799')

Filled 5 1/2 csg W/sd (3780-3846) Dumped 5 sk cmt W/dump bailer. (3745-3780)

Cutoff and recovered 2906' of 5 1/2 csg.

Filled 8 5/8 csg with mud to 375' -set rock & sand bridge (350-375)

Filled with 5 yds readymix cmt from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Bio Z. Manning
Well Plugging Supervisor

INVOICED

DATE 7-28-72

INV. NO. 6062-112