

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SW-865-9E

SEC. 5 TWP. 20 RGE. 16-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Otto Rankin

Operator Gen. F. Brack Oil Co. Inc. Address 310 Brown Bldg. Wichita-Kans

Field _____ County Rawlree

Total Depth 3795 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 3/4 - 1804 ft. Circulated with cement
5 1/2" casing set at 3795 ft. 125 sacks of cement.
Plugged back to 3765 ft. with shot-blushed.
5 sacks of cement at 3765 ft. Shot off & pulled
the 5 1/2" casing - mud to 250 ft. Set Arch Bridge
to 15 sacks of cement at 250 ft. - mud to 25 ft -
Bridge & 10 sacks of cement at the surface.

PLUGGING
FILE NO. 5, 120, 160
BOOK PAGE 130, LINE 12

RECEIVED
District Conservation Agent
Date DEC - 8 1951
12 - 8 - 51