

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 107-38

LOCATION NE-SE-22E

SEC. 11 TWP. 20 RGE. 16-W

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease George Knoche

Operator Magnolia Petco. Co. Address Box #770 - G. Bend - Kans.

Field _____ County Pawnee

Total Depth 3754 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 1040 ft. Circulated with cement
7" casing set at 3724 ft - Filled back from bottom
to 3700 ft with chat - 16 sacks of cement dumped at
3700 ft - Shot off & pulled the 7" casing - Filled with
mud to 250 ft - Rock bridge & 20 sacks cement at 250 ft
Mud to 30 ft - R. bridge & 10 sacks of cement
at the surface*

Bob Mullins

Plugging Contractor

RECEIVED

Conservation-Div.

C. D. Stough

District Conservation Agent

AUG 9 - 1949

Date 8-6-49

STATE CORPORATION
COMMISSION
KANSAS

PLUGGING
FILE SEC 11 TWP 20 RGE 16W
BOX PAGE 107 LINE 38