

15.145.00529.0000

Form CP-3  
Rev. 6-26-62

*40*  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 20 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Imperial Oil of Kansas  
Complete Address: 780 4th Natl Bk Bldg Wichita, Kansas  
Lease Name Crawford Well No. 1  
Location SE SE NW Sec. 16 Twp. 20 Rge. (E) (W) 16  
County Pawnee Total Depth 3958  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: same & Globe Cementing Co  
Address:      License No.       
Operation Completed: Hour 2:30PM Day 18 Month 5 Year 63

The Above well was plugged as follows:

8 5/8" 310' circulated with cement.

Circulated hole with heavy mud, set plug at 450', displaced 20 sax  
cement through drill pipe, heavy mud to 240', set plug and displaced  
20 sax cement through drill pipe, heavy mud to 40', set plug, hulls  
and filled to bottom cellar with cement.

Cementing by Globe Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *Edwin Ledy*  
Well Plugging Supervisor

DATE 5/21/63  
INV. NO. 9112-W