

WELL PLUGGING APPLICATION

Operator: Phillips Petroleum Company License# 5229

Box 287 Great Bend, KS 67530

Plugging Contractor: Kelso Casing Pulling License# 6050

Lease Name Welch Repressuring System Well# W-16 API# _____

Location C SE NE Sec. 21 Twp. 20S Rge. 6W County Rice West

Total Depth 3437' Plug Back 3379' Pipe Size 5 1/2" 14#

Type of Well: Oil _____ Gas _____ Input XX Disposal _____ D&A _____

Other well history: 8 5/8" casing set at 164' w/140 sx. circulated to surface.
5 1/2" 14# set at 3387' w/50 sx.
Perforated 3367-3375' (Mississippi).
Converted to water injection 06-24-78

Well Log available? Yes X No _____

Driller's log and Lane wells PFC Log.

Date you desire to plug September 10, 1984

Why was well abandoned? Fry "C" Lease was shut down as uneconomical to operate (the lease will be plugged and abandoned). This injection well served only the Fry "C" Lease and is no longer needed for operation.

Condition of well: Mechanical condition - good.

RECEIVED
STATE CORPORATION COMMISSION

Operators suggested method of plugging well.

SEP 11 1984

CONSERVATION DIVISION
Wichita, Kansas

Bottom: Bridge off perforations, then dump bail 5 sx cement to fill to approximately 3320'. Shoot casing free at approx. 2500', (free point). Pull casing, then pump approx. 80 bbls mud with hulls.

Top: Pump 160 sx 50-50 Pozmix w/6% gel and 3% CaCl to fill surface and extend to top of Hutchinson salt (approx. 480').

The joint office will reply to this information within 72 hours.

A field technician will work with the operator on plugging this well.

302 W. McArtor Road
Dodge City, Kansas 67801

Forbes Field
Topeka, Kansas 66620

202 Century Plaza Building
Wichita, Kansas 67202

2501 Market Place
Salina, Kansas 67401

1 West Ash
Chanute, Kansas 66720

1014 Cody
Hays, Kansas 67601

RECEIVED
KCC-KDHE

SEP 4 1984

JOINT OFFICE #5
Salina, KS

Handwritten initials

Handwritten number 5



JOHN CARLIN
MICHAEL LENNEN
R. C. (PETE) LOUX
PHILLIP R. DICK
JUDITH MCCONNELL
BRIAN J. MOLINE

GOVERNOR
CHAIRMAN
COMMISSIONER
COMMISSIONER
EXECUTIVE SECRETARY
GENERAL COUNSEL

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

September 27, 1984

DEC 27 1984

WELL PLUGGING NOTICE

EXPIRES

Welch Repressuring Sytem W-16
C SE NE
Sec. 21-20S-6W
Rice County

Phillips Petroleum Company
Box 287
Great Bend, KS 67530

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

Jack M. McCord, Director

Please submit your proposal for plugging the above captioned well to
DIST. #5 2501 Market Place, Ste. D Salina, KS 67401
five days prior to plugging the well (KAR-82-3-113).