

STATE OF KANSAS  
KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION  
130 South Market - Room 2078  
Wichita, Kansas 67202

15.009.23831.0000

FORM CP-1 (3/92)

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and File ONE Copy)

API # 154009-23,831 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Turnco Drilling, Inc. KCC LICENSE # 30517  
(owner/company name) (operator's)

ADDRESS Rt. 1 Box 129J CITY Great Bend

STATE Kansas ZIP CODE 67530 CONTACT PHONE # (316) 792-6144

LEASE Weathers "C" WELL# 1 SEC. 29 T. 20 R. 13W (East/West)

C. N/2 NW SW SPOT LOCATION/QQQQ COUNTY Barton

\_\_\_\_\_ FEET (in exact footage) FROM S/N (circle one) LINE OF SECTION (NOT Lease Line)

\_\_\_\_\_ FEET (in exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL \_\_\_\_\_ D&A \_\_\_\_\_ SWD/ENHR WELL \_\_\_\_\_ DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE \_\_\_\_\_ SET AT \_\_\_\_\_ CEMENTED WITH \_\_\_\_\_ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 366' CEMENTED WITH 275 SACKS

PRODUCTION CASING SIZE 5-1/2" SET AT 3452' CEMENTED WITH 100 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: Perfs: 3335-3408

ELEVATION 1890 1900 T.D. 3455' PBSD \_\_\_\_\_ ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR \_\_\_\_\_ CASING LEAK \_\_\_\_\_ JUNK IN HOLE \_\_\_\_\_

PROPOSED METHOD OF PLUGGING \_\_\_\_\_ ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS. 12-10-98

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NO IS ACO-1 FILED? \_\_\_\_\_

If not explain why? Unavailable

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Bill Gann

PHONE# (316) 792-6144

ADDRESS Rt.1 Box 129J City/State Great Bend, Ks. 67530

PLUGGING CONTRACTOR Mike's Testing & Salvage Inc. KCC LICENSE # 31529  
(company name) (contractor's)

ADDRESS P.O. Box 467 Chase, Kansas 67524 PHONE # ( ) (316) 938-2943

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) ASAP


PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 12-8-98

AUTHORIZED OPERATOR/AGENT: Mike Gann  
(signature)

REPLACEMENT CARD

BROUGHER OIL, INC. 29-20-13W  
 P.O. DRAWER 1367 #1 'C' WEATHERS C. N/2 NW SW  
 GREAT BEND, KS. 67530  
 CONTR MOHAWK DRILLING, INC. CITY BARTON  
 GEOI LARRY BOOKLESS FIELD HLSS  
 ELV 1900 KB SPD 12/27/84 CARD 5/30/85 IP P 15 RO & 10 BWPD  
 1890 GL DRLG COMP 1/4/85 LRC 3335-3408 OA  
 API 15-DD9-23,837



LOG	Top	Depth/Datum	
TOP	2776	- 876	B 5/8 " 366 / 275 SX, 5 1/2 " 3452 / 100 SX
HEED	3081	-1181	NO CORES
TOR	3100	-1200	DST (1) 3702-3250 (LKC) / 45-45-45-15, GTS / 8", GA 449
DOUG	3117	-1217	MCFGPD & STAB, REC 340' GCM, SIP 220-220#, FP 120-160 / 140-160#, HP 1762-1703#, BHT 102"
BR LM	3196	-1296	DST (2) 3250-3285 (LKC) / 45-45-45-45, GTS / 22", GA 4.84
LANS	3205	-1305	MCFGPD & STAB, REC 70' GCM, SIP 240 240#, FP 40 60 / 60-60#, HP 1703-1703#, BHT 95"
BKC	3420	-1520	DST (3) 3288-3300 (LKC) / 45-45-45-45, 124' SLI OIL & GCM,
CONG	3423	-1523	SIP 280-320#, FP 20-40 / 60-60#, HP 1723-1703#, BHT 98"
GRAN WSH	3428	-1528	DST (4) 3341-3380 (LKC) / 45-45-45-45, GTS / 40", GA 9.415
GRAN	3440	-1540	MCFGPD & STAB, REC 570' HVY OILY GCM, 120' CLEAN GSY
LTD	3452	-1552	OIL, SIP 837-797#, FP 80-180 / 180-240#, HP 1807-1768#, BHT 96"
RTD	3455	-1555	DST (5) 3386-3430 (LKC) / 45-60-45-60, REC 30' SLI OIL & GCM, 120' HO & GCM, SIP 319-260#, FP 60-80 / 80-100#, HP 1821-1762#, BHT 98"

COPYRIGHT 1985  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS

INFO RELEASED: 6/14/86 - WAS OIL WELL - TIGHT HOLE  
 (over)

BROUGHER OIL, INC. #1 'C' WEATHERS 29-20-13W  
 C. N/2 NW SW

DST (5) 3430-3443 (GRAN) / 60-45-60-45, 120' GCM, REC 30' SLI OIL & GCM, SIP 100 80, FP 10-30 30 30#, HP 1827-1767#, BHT 100"  
 MICT. - CO. PF (LKC) 3402-3408 W / 2 3/4", AC 500 GAL (15% MCA), SWB 20 OF 10 MIN. DE AC 1500 GAL (28% NE), SWB 6 6 HO / 30", SPI HET DP AT 3496, PF (LKC) 3396-3390 W / 2 5/8", AC 500 GAL (15% MCA), SWB 53 58 BF, TST 6 38 BF / 60", 5 22 BF / 12", 2 21 BF / BP AT 3376, PF (LKC) 3372-3375, 3370-3372, W / 2 5/8", AC 750 GAL (15% SGA), SWB 65 85 BF, SWB 2 41 BF / 60", PLUG 1 2N W / 10-BF W / ROCK SALT & AC OTHER ZN W / 250 GAL (15% NE), SWB 4 53 BF (95% OIL) / 60", 2 82 BF (70% OIL) / 120", RE-AC 2000 GAL (15% SGA), SWB 12 28 BF (70% OIL) / 120", SPI HET DP AT 3352, PF (LKC) 3375-3375, W / 2 5/8", AC 500 GAL (28% NE), SWB 7 52 BF / 1 1/2", DE AC 1000 GAL (28% NE), SWB 17 12 BF (70% OIL) / 1 1/2" SGA, ONFO 350' OIL, PULL PLUG, POP, P 15 RO & 10 BWPD

*Prize*  
 This is the only weather  
 that I have  
 Cookie

RECEIVED  
 KANSAS CORP CO. INC.  
 DEC 10 1988



## Kansas Corporation Commission

*Bill Graves, Governor   John Wine, Chair   Susan M. Seltsam, Commissioner   Cynthia L. Claus, Commissioner*

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

December 11, 1998

Turnco Drilling, Inc.  
Rt. 1, Box 129J  
Great Bend, Ks. 67530

Weathers C #1  
API 15-00923831  
N/2 NW SW  
Sec. 29-20S-13W  
Barton County

Dear Bill Gann,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

David P. Williams  
Production Supervisor

District: #4  
2301 E 13th  
Hays KS 67601  
(913) 628-1200