



JOHN CARLIN  
Governor  
R. C. LOUX  
Chairman  
JANE T. ROY  
Commissioner  
WILLIAM G. GRAY  
Commissioner  
Carol J. Larson, Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

May 6, 1980

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
AUG - 5 1980  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Bruck  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Willard Brucker of Blackstone Drilling, Inc has this date requested permission to plug the following described well:

Mr. Brucker guarantees payment of the plugging fee.

Operator's full Name: H/Fred D. Koehn

Complete Address: R#2, Box 89, Galva, Kansas 67443

Lease Name: College Well No. 1

Location: SE SE SW Sec. 13 Twp. 20 Rge. 2 (E) (W) X

County: McPherson Total Depth 2990' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Brucker was instructed to plug the well as follows:

8 5/8" - 133' - cem. circ - Fill hole with mud to 125'. Push plug and 1/2 sack hulls to 125' and cement hole with 20 sacks cement. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rat hole and cement with 2 sacks.

Very truly yours,

Conservation Division Agent

Copy:  
Original mailed 5-8-80