



15.159.30244.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

May 19, 1966
RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

MAY 26 1966

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Olin Kelso of Sterling Drilling Company has this
date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Plains Exploration Company

Complete Address: 1135 Petroleum Club Bldg., Denver, Colorado

Lease Name: Olander Well No. 1

Location: C NE SE Sec. 16 Twp. 20 Rge. 6 (E)(W) X

County Rice Total Depth 3373' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Kelso was instructed to plug the well as follows:

Fill hole with mud to 150'. Push plug and $\frac{1}{4}$ sack hulls to 150' and
cement hole with 20 sacks through drill pipe. Fill hole with mud to
40'. Push plug and $\frac{1}{2}$ sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent