



15.159.30183.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

September 19, 1965

RECEIVED  
STATE CORPORATION COMMISSION

SEP 23 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Jack Flake of Woodman-Iannitti Drlg. Chas this

date requested permission to plug the following described well:

Mr. Flake guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name: Hunter Well No. 1

Location: NE NW SW Sec. 3 Twp. 20 Rge. 7 (X) (W) X

County Rice Total Depth 3685' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Flake was instructed to plug the well as follows:

Fill hole with mud to 225'. Push plug and 1/4 sack hulls to 225' and cement hole with 25 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/4 sack hulls to 40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,

*Robert J. Loman*  
Conservation Division Agent