



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1973

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ross Crawford of Red Tiger Drilling Co. has this
date requested permission to plug the following described well:Mr. Crawford guarantees payment of the plugging fee.Operator's full Name: Messman-Rinehart Oil CompanyComplete Address: 1432 Wichita Plaza, Wichita, Kansas 67202Lease Name: Wahl "A" Well No. 1Location: SW NW NE Sec. 3 Twp. 20 Rge. 7 (E) (W) XCounty: Rice Total Depth 3375' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Crawford was instructed to plug the well as follows:Fill hole with mud to 255'. Push plug and 1/4 sack balls to
255' and cement hole with 25 sacks cement through drill
pipe. Fill hole with mud to 40'. Push plug and 1/2 sack
balls to 40' and cap hole with 10 sacks cement.
Bridge rat hole and cement with 2 sacks cement.

Very truly yours,


Conservation Division Agent