

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hayes of Alpine Oil has this date requested permission to plug the following described well:

Mr. Hayes guarantees payment of the plugging fee.

Operator's full Name: Alpine Oil & Royalty Co., Inc.

Complete Address: 800 Bitting Bldg., Wichita, Ks.

Lease Name: Stieben Well No. 1

Location: C NE SE Sec. 8 Twp. 19 Rge. 21 (E)(W) X

County: Ness Total Depth 4400' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Hayes was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sc cement thru drill pipe. Heavy mud to 300' set cementing plug and
displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

RECEIVED
STATE CORPORATION COMMISSION
OCT 14 1968
CONSERVATION DIVISION
Wichita, Kansas

Very truly yours,
Leo F. Massey
Conservation Division Agent