

Form CP-3
Rev. 6-4-68

KANSAS
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

SEP 18 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Mull Drilling Company, Inc.

Complete Address 415 Page Court, -220 W. Douglas, Wichita, Kansas 67202

Lease Name McKitterick (SWD) Well No. 1

Location C SW NW Sec. 33 Twp. 17 Rge. (E) (W) 21

County Ness Total Depth 4236'

Abandoned Oil Well Gas Well Input Well SWD Well XX D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Eng., Inc.

Address Box 698, Great Bend, Kansas License No. 670

Operation Completed: Hour 4:30 P Day 16 Month 9 Year 1975

The above well was plugged as follows:

Total Depth 4236' 8 5/8 csg set 364' cwc 180 sx.

5 1/2 csg set 1467' cw 250 sx cem. Top perf. 1040'.

Cutoff & recovered 605' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 10 sk gel & water W/300 lbs hulls ^{released plug} -70 sk

50-50 poz 2% -displgead with 8 sk gel & water & capped with 20 sk 50-50 poz 2%.

by Allied Cementing Co. PP 800 lbs. SIP 800 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 9-23-75
INV. NO. 1939-W

Signed: Leo Massey
Well Plugging Supervisor