

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 20 1965

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Clem Boston of Pickrell Oil Co. has this  
 date requested permission to plug the following described well:

Mr. Boston guarantees payment of the plugging fee.

Operator's full Name: Pickrell Oil Co.

Complete Address: 705 4th Natl Bk Bldg - Wichita Kans.

Lease Name: Hierman Est Well No. 1

Location: C-Nw-Ne Sec. 15 Twp. 17 Rge. 21 (E) (W)

County Wess Total Depth 4252 Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Boston was instructed to plug the well as follows:

Cir Mud at 600', set plug and dispense 25 sac  
cement thru drill pipe, heavy mud to 220'  
set plug and 20 sac cement, heavy mud to 40'  
set plug, 1/2 sac hulls and 10 sac cement

Very truly yours,

Gilbert P. Zerker  
 Conservation Division Agent