

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- 48

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name D. R. Linnick Oil Co., Inc.

Complete Address 221 So. Broadway, Suite 400, Wichita, Kansas 67202

Lease Name Frewert Well No. 3

Location SE NW SW Sec. 11 Twp. 17 Rge. 10 (~~East~~) (West)

County Ellsworth Total Depth 3277'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling and Halliburton Co.

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour: 10:00 AM Day: 29 Month: June Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows: 5 1/2" - 3235' - 75 sacks (out of hole 1200') (last shot 948') (No recovery)
Well apparently had been squeezed once. Pumped 60 sacks cement into annulus 8 1/8" - 5 1/2". Pumped 190 sacks cement into 5 1/2" casing 50 PSI. Cement dropped to 500'. Filled hole to base of cellar with 3 yards ready-mix concrete

RECEIVED
STATE CORPORATION COMMISSION
JUL 1 1982
CONSERVATION DIVISION
Wichita, Kansas

Cement used 50/50 Pozmix w/4% gel and 3% cc.

Amount of Surface Casing: 10 3/4" - 200' - 150 sacks

I hereby certify that the above plugging instructions were given as herein stated.

Signed: _____
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Present when cemented with pump truck. Not present when filled with ready-mix

INVOICED

Signed: [Signature]
Conservation Division Agent

DATE 7-1-82

INV. NO. 566-W

10650

10650
10650