

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Banner Oil Company

Complete Address Box 316, Claflin, Kansas 67525

Lease Name Peterman Well No. 2

Location SE NE NE Sec. 11 Twp. 17 Rge. 10 (E) (W) X

County Ellsworth Total Depth 3297'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas License No. 462

Operation Completed: Hour 3 PM Day 24 Month April Year 1968

The above well was plugged as follows:

Hole filled with sand to 3250' and cemented with 5 sacks. 5 sacks gel mud pumped through 5 1/2" casing at 600'. 25 sacks cement pumped through casing at 500'. 5 sacks gel mud pumped through casing at 325'. 25 sacks cement pumped through casing at 225'. Hole filled with mud to 40'. Rock bridge set from 40' to 30' and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4/29/68

INV. NO. 7650-W