

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-053 20,606

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Petroleum Energy, Inc.

Complete Address 710 One-Twenty Bldg., Wichita, Kansas 67202

Lease Name Krenke "A" Well No. 1

Location C S/2 S/2 NE Sec. 11 Twp. 17 Rge. 10 (~~EAST~~) (West)

County Ellsworth Total Depth 3290'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling and Allied Cementing Co., Inc.

Address Box 176, Chase, Kansas License No. 683

Operation Completed: Hour: 2:45 PM Day: 19 Month: June Year: 19 81

Plugging Operations attended by Agent? All Part None

The above well was plugged as follows: 8-5/8"-284'-175 sacks 4 1/2"-3282'-100 sacks

Hole filled with sand to 3250' and cemented with 4 sacks cement.

Hole squeezed with 4 sacks hulls, 20 sacks gel-mud, 1 sack hulls, and 100 sacks 50-50 Pozmix w/4% gel and 3% cal. chloride pumped into 8-5/8" surface casing.

2650' of 4 1/2" casing recovered.

RECEIVED
STATE CORPORATION COMMISSION

JUN 23 1981

I hereby certify that the above well was plugged as herein stated CONSERVATION DIVISION
Wichita, Kansas

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 7-21-81
INV. NO. 5879-W

106.93