

15.113.19356.0000

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 26 1961

CONSERVATION DIVISION
Wichita, Kansas

TO:
J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: McPherson

Location: NE- SW- NW- Sec. 14 Twp. 20 Rge. 4 (E) (W)

Name of Field: Groveland Total Depth: 3743'

I have this date completed supervision of plugging of:

Lease Name: F A. Lovett Well No. I

Operator's Full Name: Frank R. Black

Complete Address: P.O. Box, 150. McPherson Kansas.

Plugging Contractor R.&.D. Casing Pulling Co.,

Address: P.O. Box 572 Hutchinson Kansas, License No. 236

Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent?

Yes _____ No X

If yes how long? _____ Reason: _____

Operation Completed: Hour 3:PM Day 21 Month 7 Year 61

The above well was plugged as follows:

Filled hole W/ sand from T.D. 3743' back to 3325' bank 5' sax cement W/ dump bailer.

Shot off and pulled 5-1/2" casing. Filled hole W/ mud from 3305' back to 265' set a

15' rock bridge and 20 sax cement. Filled hole W/ mud from 180' back to 30' set 5' bridge

an 8 sax cement back to zero. 8-5/8" surface pipe 6' below ground level.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED

DATE 7-31-61

INV. NO. 4003-E