

W KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 5 1963

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Frank J. Black Oil Field Equip.

Complete Address: Box 150, McPherson, Kansas

Lease Name Hollaway Well No. 1

Location NW NW SW Sec. 14 Twp. 20 Rge. 4 /(E) (W)

County McPherson Total Depth 3725'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 305, Chase, Kansas. License No. 436

Operation Completed: Hour 4:PM Day 2 Month 12 Year 63

The Above well was plugged as follows:

Filled hole w/ sand from T.D. 3725' back to 3710'. Ran 5 sax cement w/ dump bailer.

Shot off and pulled 5 1/2" casing. Filled hole w/ mud from 3675' back to 225'. This

well had a short string of surface pipe 185'. At this point the equus bed is 170' deep.

and the surface pipe filled up w/ equus bed water sand. We pumped in 6 sax mud and 32

sax cement at 225' Filled hole w/ mud from 150' back to 40' set a bridge and ran 10

sax cement from 35' back to zero. 8 5/8" surface pipe 5' below ground level.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/5/63
INV. NO. 8229-W

Signed: [Signature]
Well Plugging Supervisor