


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

McPherson County, Sec. 11, Twp. 20S, Rge. 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines S/2NW/11
Lease Owner Bert Self
Lease Name Lovett (W. M.) Well No. 1
Office Address R. R. #1, Hutchinson, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 19 51
Application for plugging filed April 19 66
Application for plugging approved April 19 66
Plugging commenced May 5 19 66
Plugging completed May 5 19 66
Reason for abandonment of well or producing formation Well Depleted
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well High Scott
Producing formation Viola Depth to top 3722 Bottom 3727 Total Depth of Well 3727 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

No pipe pulled. Plugged hole with 3 yards cement from 210' to 0.

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 1966

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self
Address Hutchinson, Kans.

STATE OF Kans., COUNTY OF Reno, ss.
Owner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bert Self
R. R. #1, Hutchinson, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 30th day of July, 19 66

Notary Public

My commission expires October 15, 1969

RECEIVED
STATE COMMISSION

D R I L L E R I S L O G

AUG 1 1966

Amerada Petroleum Corporation
SW SW NW 14-20S-4W
McPherson County, Kansas
#1 W. M. Lovett

CONSERVATION DIVISION
1966

<u>FROM</u>	<u>TO</u>	
0	40	Surface Clay
40	175	Sand
175	380	Shale & Shells
380	500	Salt & Shells
500	605	Lime
605	755	Shale & Lime
755	1120	Lime & Shale
1120	1155	Shale
1155	1480	Shale & Shells
1480	2490	Shale & Lime
2490	2710	Lime & Shale
2710	2780	Lime
2780	2995	Lime & Shale
2995	3060	Lime
3060	3185	Lime & Shale
3185	3251	Lime
3251	3340	Miss. Lime
3340	3385	Lime
3385	3447	Miss. Lime
3447	3505	Lime & Shale
3505	3727	Shale
	3727	ROTARY TOTAL DEPTH

COMMENCED: 2-19-54
COMPLETED: 3-7-54

CASING RECORD

Set 8-5/8" surface casing at
606' with 150 sacks cement.

LOG TOPS:

Lansing 2542
Miss 3194
Kind 3480
Maquoketa 3707
Viola 3721

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I hereby affirm that the above and foregoing is a true and correct copy of the log of the #1 W. M. Lovett located in Section 14-20S-4W, SW SW NW in McPherson County, Kansas.

ANSCHUTZ DRILLING CO., INC.

BY E. G. Koelling
E. G. Koelling

Subscribed and sworn to before me this 18th day of March, 1954.

Wilma W. Shipman
Notary Public

My Commission Expires: March 24
~~March 21~~, 1956.

14-20-4W

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 1966

AMERADA PETROLEUM CORPORATION

BID NO. 18

CONSERVATION DIVISION
Wichita, Kansas

Name of Lease:

W. M. Lovett Lease described as the west twenty acres of S/2 NW/4 of Section 14, 20S - 4W, McPherson County, Kansas, containing twenty acres more or less.

Ownership:

Amerada Petroleum Corporation owns and is selling the full 7/8ths working interest in oil and gas rights.

Status of Wells
as of 11-1-65:

Well No. 1 was pumping. Saltwater Disposal Well No. 1 was not in use. Saltwater Disposal Well No. 2 was taking water. In October, well pumped 124 barrels oil and 2945 barrels water in 744 hours. Recent test: 5 barrels oil per day and 95 barrels water per day.

Producing Horizon
and Depth:

Well No. 1 - 3,727' T.D. Completed in Viola Lime in March 1954 through open hole 3,722 to 3,727'. Set 13-3/8" OD casing at 254' with 200 sacks cement, cement circulated; 8-5/8" OD at 604' with 385 sacks, cement circulated. 5-1/2" OD at 3,722' with 150 sacks.

Log

Saltwater Disposal Well No. 1 was drilled to 707' T.D. but is not now in use.

Saltwater Disposal Well No. 2 was drilled to 497' and is presently taking water from Lovett No. 1 and from Warner-Stevenson Creig No. 1

Great Check
12-18-65

Bew:
Amerada will
send log
S.S.G.