

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County, Sec. 14 Twp. 20 Rge. 4 (E) W (W)

T - 20 NORTH R - 4W

Location as "NE/CNW%SW%" or footage from lines NW NW SW

Lease Owner Frank J. Black

Lease Name Holloway Well No. 1

Office Address McPherson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 11-1-63 19

Application for plugging filed 10-28-63 19

Application for plugging approved 10-29-63 19

Plugging commenced 11-1-63 19

Plugging completed 12-2-63 19

Reason for abandonment of well or producing formation Depleted.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Cecil Jones

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3725 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	185'	None
				5-1/2"	3719'	2490'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3710' and dumped 5 sacks of cement with dump bailer. Pulled 5 1/2" casing. Tried to bail hole down, sand came in. Ran tubing to 225' and pumped 6 sacks of mud and 32 sacks of cement @ 225'. Bailed hole dry, mudded to 30' and capped well with 8 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1963

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY License #436

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.

Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight

Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of December, 1963

Milton J. Volin
Notary Public.

My commission expires May 20, 1964

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-113-00033-0000

Company- ANSCHUTZ DRILLING COMPANY
Farm- Holloway No. 1

SEC. 14 T. 20 R. 14W
NW NW SW

Total Depth. 3725
Comm. 10-17-53 Comp. 11-1-53
Shot or Treat. J.
Contractor.
Issued. 3-5-55

County McPherson
KANSAS



CASING:

8 5/8" 185' cem. w/150 sx
5 1/2" 3719' cem. w/150 sx

Elevation. 1474 RB

Production. 141 BO & NW

Figures indicate Bottom of Formations.

shale & sand	240
shale & shells	465
shale & lime	612
Anhydrite	635
salt	665
lime	802
shale & shells	815
lime	1115
sdy lime & shale	1140
lime	1175
shale & lime	1310
shale	1450
shale & lime	1665
shale & shells	1830
shale	2000
lime, shale & sand	2090
lime	2337
shale	2433
lime	2445
shale & lime	2540
lime	3055
shale & lime	3115
sandy shale	3157
shale	3196
lime	3373
chert & lime	3410
shale, lime & chert	3438
lime	3515
shale & lime	3570
shale	3719
Viola	3725
Total depth	

Tops:	
Lansing	2541
Mississippi	3196
Kinderhook	3474
Maquoketa	3704
Viola	3719

Drill Stem Test: 3716-25, open 1 hr,
recovered 110' free oil, 30' muddy oil,
BHP 1260#, closed 15 min.

RECEIVED
STATE CORPORATION COMMISSION

DEC 13 1963

CONSERVATION DIVISION
Wichita, Kansas