

STATE OF KANSAS
STATE CORPORATION COMMISSION

15.145.20682.0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 1 Twp. 20S Rge. 16 ~~W~~
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines
SW NW SE

Lease Owner Sunburst Exploration Company
Lease Name ERICKSON Well No. 1


Office Address Suite 708 - One Main Place, Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202
Dry Hole

Date Well completed 7-7 1980
Application for plugging filed 7-7 1980
Application for plugging approved 7-7 1980
Plugging commenced 7-7 1980
Plugging completed 7-7 1980
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 3730'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	1018'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set,

- 1020' - 50 sx cement
- 300' - 25 sx cement
- 40' - 10 sx cement
- Rathole - 5 sx cement

7-17-80

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1980
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas - Suite 500, Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
Ernest Sifford (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ernest Sifford
401 E. Douglas Suite 500, Wichita, Ks.
(Address) 67202

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1980

CAROLYN J. TJADEN
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Expires Sept. 5, 1980

Carolyn J. Tjaden
Notary Public.

My commission expires

DRILLERS LOG

OPERATOR: SUNBURST EXPLORATION, Suite 708 - One Main Place, Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name Erickson Well No. 1

Sec. 1 T. 20S R. 16W Spot SW NW SE

County Pawnee State Kansas Elevation

Casing Record: 385 sx HCL 3% CC
Surface: 8 5/8" @ 1018' with 200 sx Class A 3% CC Sxs.

Production: @ with Sxs.

Type Well: D & A Total Depth 3730'

Drilling Commenced: 6-27-80 Drilling Completed 7-6-80

Formation	From	To	Tops
Cellar	0	7	Arbuckle - 3700'
Top soil, sand	7	35	
Shale, Lime (strks)	35	384	
Dakota sand	384	550	
Shale, Lime (strks)	550	814	
Shale	814	1011	
Anhydrite	1011	1019	
Shale	1019	1381	
Sandy Shale	1381	1920	
Shale, Lime (strks)	1920	2880	
Lime	2880	2892	
Shale, Lime	2892	3685	
Lime	3685	3700	
Chert	3700	3730	

RECEIVED
STATE CORPORATION COMMISSION
JUL 17 1980
CONSERVATION DIVISION
Wichita, Kansas

COMPLETION RECORD

Liner Record: Size From To

Cementing Record: Sacks

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production:

Electric Log Type and Depths Covered