

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-145-21,116-0000

LEASE NAME Fleske

WELL NUMBER #1

SPOT LOCATION SW NE NE

SEC. 3 TWP. 20S RGE. 16 XXXX (W)

COUNTY Pawnee

Date Well Completed 5-13-84

Plugging Commenced 5-13-84

Plugging Completed 5-13-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Yost Oil Operations

ADDRESS Box 811, Russell, KS 67665

PHONE # (913) 483-6455 OPERATORS LICENSE NO. 6343

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #1

Is ACO-1 filed? No If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 3783' (RTD)

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

Formation	Content	From	To	Size	Put In	Pulled out
		-0-	318'	8 5/8"	318'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Mud laden fluid @ 3783'-3700' 10 sks cement @ Mousehole
50 sks cement @ 3700'
50 sks cement @ 1030' (Additional 250 ASC sks pumped down
50 sks cement @ 400' surface to control water flow as per
10 sks cement @ Rathole state pluggers order, pluggers on location.)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Emphasis Oil Operations License No. 750
 Address Box 506, Russell, KS 67665

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1984
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Joe K. Branum (employee of operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe K. Branum
 (Address) Box 506, Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 18th day of May, 1984

Denise S. Reynolds
Denise Reynolds Notary Public

DENISE S. REYNOLDS
NOTARY PUBLIC
STATE OF KANSAS
My Appointment Expires: 2-13-85

EMPHASIS OIL OPERATIONS

P. O. BOX 506
RUSSELL, KS 67665

DRILLERS LOG

OPERATOR: Yost Oil Operations, Inc.
Box 811
Russell, KS 67665

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, KS 67665

LEASE: Fleske WELL: #1

LOCATION: SW NE NE
Section 3-20S-16W
Pawnee County, KS

ROTARY TOTAL DEPTH: 3783'

ELEVATION:

COMMENCED: 5-05-84

DATE COMPLETED: 5-13-84

CASING: 8 5/8" @ 318' with 200 sks cement

STATUS: Dry Hole

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	40'	Shale	2457'
Sand & Shale	321'	Shale & Lime	3687'
Shale	1031'	Lime (RTD)	3783'
Anhydrite	1046'	Log TD	3786'

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)


Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum

Joe K. Branum

Subscribed and sworn to before me this 18th day of May, 1984.

My Commission Expires: February 13, 1985.



Denise S. Reynolds

Denise S. Reynolds, Notary Public

RECEIVED
STATE CORPORATION COMMISSION

MAY 21 1984

CONSERVATION DIVISION
Wichita, Kansas