


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Pawnee County. Sec. 3 Twp. 20 Rge. 16 (E) (W) W

Location as "NE/CNW/SW" or footage from lines NE NW NE  
Lease Owner Ben F. Brack Oil Co., Inc.  
Lease Name Fleske Well No. 1  
Office Address 310 Brown Bldg, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Gas  
Date well completed March 21, 1957  
Application for plugging filed Feb 9, 1957  
Application for plugging approved Feb 9, 1957  
Plugging commenced Feb 11, 1957  
Plugging completed Feb 15, 1957  
Reason for abandonment of well or producing formation Gas Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production Dec 1956  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. M. Brundage  
Producing formation Arbuckle Depth to top 3691 Bottom 3741 Total Depth of Well 3741 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface soil, clay, sand shale, shells, red beds, and anhydrite		0		8 5/8	856'	None
Lansing Arbuckle		3691		5 1/2	3740	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Ran bailer, measured hole, clean out cellar, removed slips from braden head. Plugged back with sand to 3680', dumped 5 sacks of cement with dump bailer. Ran 25 sacks of mud and 100 sacks of cement by Halliburton Oil Well Cementing Company. Top of cement standing at top of surface pipe.

RECEIVED  
COMMISSION  
1957 3-21-57  
CONSERVATION DIVISION  
KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor E & L Casing Pulling Co.  
Address 1003 Heizer Street, Great Bend, Kansas

STATE OF Kansas COUNTY OF Sedgwick ss.  
Bernard D. Grant (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bernard D. Grant  
310 Brown Bldg Wichita Kan (Address)

SUBSCRIBED AND SWORN TO before me this 27<sup>th</sup> day of February, 1957

My commission expires December 27, 1960  
Jean Carman Notary Public.

24-7368-5 3-53-20M

PLUGGING  
FILE SEC 3 T 20 R 16W  
BOOK PAGE 139 LINE 24

## D R I L L E R ' S L O G

Operator:  
Ben F. Brack Oil Co. Inc.  
Wichita, Kansas

FLESKE #1  
NE NW NE 3-20-16W  
Pawnee County, Kansas

Contractor:  
Company tools

Started: 3-2-51  
Completed: 3-18-51

Surface soil, shale & shells	0	- 200	
Shale & Shells		470	
Red Beds		775	
Red Bed Shale		853	
Anhydrite		1065	
Salt & shale		1780	
Shale & Lime		2150	
Lime & Shale		2485	
Shale & Lime		3325	8 5/8" set at 853'
Lime & Shale		3415	5 1/2" set at 3740'
Lime		3470	
Top of arbuckle		3691	
Lime		3750	TD

CASING RECORD

Depths denote bottoms of formations.

To the best of my knowledge, the above  
is a true and correct statement of the  
formations and where found.

BEN F. BRACK OIL COMPANY, INC.

By

*Bernard W. Gierck*  
Vice-President

Dated: March 25, 1957

Witnessed: *Jean Gorman*

RECEIVED  
STATE CORPORATION COMMISSION

MAR 26 1957

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 3 T 20 R 16W  
BOOK PAGE 139 LINE 24