

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County. Sec. 9 Twp. 20 Rge. 5 (X) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner Sierra Petroleum Co., Inc.

Lease Name Anderson Well No. #1

Office Address 420 West Douglas, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 7/30/56 19

Application for plugging filed 7/29/56 19

Application for plugging approved 7/30/56 19

Plugging commenced 7/30/56 19

Plugging completed 7/30/56 19

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3450' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	203'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLUGGING REPORT

Filled hole with heavy mud from 3450' up to 195'. Filled with hulls, wood plug and 15 sacks cement through drill pipe from 195' to 165'. Filled with heavy mud from 165' to 40'. Filled hole from 40' to cellar - 0' - with hulls, wood plug and 5 sacks cement. Job completed at 4:30 PM 7-30-56.

Mr. Durkee agent

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sierra Petroleum Company, Inc.

Address 420 West Douglas, Wichita, Kansas

STATE OF KANSAS, COUNTY OF RUSSELL, ss.

C. L. Honaker (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. L. Honaker

Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 31st day of July, 19 56

My commission expires 10-17-59

Leroy Harty
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG 5 1956 8-3-56

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 9 T. 20 R. 5W
BOOK PAGE 85 LINE 24

SIERRA PETROLEUM COMPANY, INC.
Anderson #1.

NW NW SW 9-20-5W
McPherson County, Ks.

Total Depth: 3450'

Elev: 1557 KB

Comm: 7/20/56
Comp: 7/30/56

Casing
8 5/8" @ 203'

Cement
135 sacks Bulk

FORMATION	DEPTH
Clay, redbed & shale	185
Redbed & shale	440
Shale, shells & salt	786
Anhydrite	803
Shale & lime	1205
Lime	1410
Shale & lime	2764
Lime	3056
Lime & shale	3122
Lime	3203
Lime & shale	3415
Cherty Lime	3434
Lime & shale	3450

TOPS: Heebner	2547-990
Brown Lime	2732-1175
Lansing	2754-1197
Mississippi	3407-1850

STATE OF KANSAS)
) SS:
COUNTY OF KANSAS)

I hereby certify that the above information is true and correct to the best of my knowledge.

C. P. Honaker

Subscribed and sworn to before me this 31st day of July, 1956

Leroy Dietz

Notary Public

My commission expires: 10-17-59

RECEIVED
THE CONSERVATION COMMISSION
AUG 3 1956
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 9 T. 20 R. 5W
BOOK PAGE 85 LINE 24