

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

15.159.20483.0000

Rice County, Sec. 3 Twp. 20S Rge. 7W (E) (W) X

Location as "NE/CNW/SW" or footage from lines
Lease Owner Messman-Rinehart Oil Company
Lease Name Wahl "A" Well No. 1
Office Address 1432 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) D & A
Date well completed November 22, 1973
Application for plugging filed November 22, 1973
Application for plugging approved November 22, 1973
Plugging commenced November 22, 1973
Plugging completed November 22, 1973
Reason for abandonment of well or producing formation D & A

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Toman
Producing formation Depth to top Bottom Total Depth of Well 3375 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	262.32'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 255', plug w/1/2 sk. hulls & 25 sx. cmt.
Mud to 40', plug w/10 sx. cmt.
2 sx. cmt. in rathole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 4 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Red Tiger Drilling Company
Address 1720 Wichita Plaza, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick
Linda H. Dickens (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Linda N. Dickens
1720 Wichita Plaza, Wichita, Kansas 67202

(Address)


SUBSCRIBED AND SWORN TO before me this 26th day of November, 1973

My commission expires

May 24, 1977

Linda C. Mowrey

Notary Public.



Mailed 12-31-73

DRILLERS LOG

No. 1 Well "A"

CASING RECORD:

8-5/8" @ 262.32'
w/155 sx cement

COMPANY:

Messman-Rinehart Oil Co.

DESCRIPTION:

SW NW NE
3-20S-7W
Rice County,
Kansas

CONTRACTOR:

Red Tiger Drilling Co.

COMMENCED:

November 15, 1973

COMPLETED:

November 22, 1973

TOTAL DEPTH: 3375'

ELEVATION:

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Hole	0	40	
Shale	40	150	
Redbed & Shale	150	222	
Anhydrite	222	227	
Redbed	227	263	
Shale	263	875	
Salt & Shale	875	1047	
Lime	1047	1085	
Lime & Shale	1085	2554	
Lime	2554	2700	
Lime & Shale	2700	2860	
Lime	2860	3317	
Mississippi, Lime & Chert	3317	3327	
Lime & Shale	3327	3375	

RECEIVED
STATE CORPORATION COMMISSION
JAN 2 1974
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

RED TIGER DRILLING COMPANY

Linda H. Dickens
Linda H. Dickens

Subscribed and sworn to before me this 26th day of November, 1973.

Linda C. Mourey
Notary Public

My Commission Expires:

May 24, 1977

